Corrigendum for IITPKD/ADMN/017/2018

Clarifications :

1. **Scope of work, pg 6:** IIT Palakkad will lay the optical fibre cables. Installation, testing and commissioning of ALL other items listed in this tender will be done by the successful bidder.

2. **Regarding "on-loan" items, pg 8 pt 10:** Cost (if any) for providing switches on loan must be listed as a separate item in the financial bid. This cost **will** be included in the determination of L1.

3. **A3 pt 2, A4 pt 2, A6 pt 2:** Read "PoE/PoE+" to mean "either PoE OR PoE+"

Changes :

Sl. No.	Existing Condition	To be read as
1.	A2 pt 5; A3 pt 5; A4 pt 5; A5 pt 5; A6 pt 5	At least 512 MB RAM, 4 MB Packet buffer size or higher
2.	A2 pt 6; A3 pt 6; A4 pt 6; A5 pt 6; A6 pt 6	Should support at least 16000 MAC addresses
3.	A4, pt 3 ... (1G Base-SR) ...	... (1G Base-LX) ...
4.	A7, pt 2 ... supporting at least 128 access points ...	... supporting at least 100 access points ...
5.	A7, pt 6 and pt 12	Shall support capability to minimize wireless interference.